

---

# MITCHELL ASSOCIATES ARCHITECTS

---

ADDENDUM NUMBER ONE TO BIDDING DOCUMENTS

COB BID NO. 2023-002

**ADDITION & RENOVATION TO  
BEACON FIRE STATION  
1140 WOLCOTT AVENUE  
BEACON, NY 12508**

Date: April 4, 2023

Site Address: 1140 Wolcott Avenue  
Beacon, NY 12508

Owner: City of Beacon, NY

Architect: Mitchell Associates Architects (MAA)  
29 Thacher Park Road  
Voorheesville, NY 12186  
Phone: 518-765- 4571  
Fax: 518-765-2950

TOTAL PAGES (Including Cover Page): 6, not including attachments.

**NOTE: ALL BIDDERS MUST EMAIL A CONFIRMATION OF RECEIPT OF THIS ADDENDUM.  
PLEASE PRINT COMPANY NAME, SIGN AND DATE THIS COVER PAGE AND SCAN AND EMAIL  
TO THE ARCHITECT, MAA. T. 518-765-4571, F. 518-765-2950 EMAIL - CECILE@MITCHELL-  
ARCHITECTS.COM.**

Company Name \_\_\_\_\_ Date \_\_\_\_\_  
(Please Print)

Signature \_\_\_\_\_

The information described herein as Addendum Number One, is hereby made addenda to all previously issued construction documents related to the Project and shall be incorporated into the Scope of the Base Bid. These pages shall be attached to the Project Manual.

GENERAL INSTRUCTIONS

- A. This Addendum Constitutes part of the Specifications and Contract. Should conflict occur between the specifications and items in this Addendum or between drawings and this Addendum, this Addendum shall govern.
- B. Bidders shall carefully examine all items and determine for themselves what subcontractors are affected and notify all bidders for subcontracts of changes, explanations, interpretations, or additions affecting their work.
- C. Work described in this Addendum shall be in accordance with specifications for like items in remainder of building and complete with all labor and materials required.
- D. Bidders are required to attach a copy of this Addendum to the specifications in their possession.
- E. Not all of the questions sent in by RFI are in this addendum. There will be additional addenda after this & any remaining questions will be answered in those addenda.
- F. **The bid date, location and time ARE changed by this Addendum.**

**\*\*\*\* Bid Date and Time is Changed to 2:00 p.m. local time, Friday, April 21, 2023. \*\*\*\***

QUESTIONS

Q: Can we get a copy of the sign-in sheet from the Pre-bid meeting?

A: The sign-in sheet is attached to the end of this addendum as A2.1 & A2.2.

Q: Is there a plan holders list available?

A: The official plan holders list can be found at the printer's web site. The link is:

[www.mitchellarch.biddyhq.com](http://www.mitchellarch.biddyhq.com)

Plan holders lists may also be found on other plan room web sites, such as Bidnet, NYS Contract Reporter, Construct Connect, Construction Journal, Dodge Construction Network, the Blue Book.

Q: There is no RFI due date listed in the specs. When is the latest date RFI's can be submitted?

A: As stated in AIA Document A701 - 2018, paragraph 3.2.2, questions must be submitted to the Architect at least seven days prior to the date of receipt of the bids, therefore, RFIs will not be accepted after 5:00 pm on April 14, 2023.

Q: Is there a construction schedule for this project. Start Date and Competition Date?

A: The construction start date will be determined after the bids are received. The duration of the project is listed in the AIA Document A132 – 2019, paragraph 3.3.1, that is bound in the Project Manual. The duration is listed as 427 calendar days.

Q: Is the trenching and backfill for the 6" combined water service by the site contractor?

A: The trenching and backfill for the 6" water main outside of the building is the responsibility of the Site Contractor.

- Q: Who is responsible for the slab removal and trenching for the new water service within room 124 mechanical room?
- A: The GC is responsible for all slab removals in the building, but each trade is responsible for their own trenching and backfilling inside of the building.
- Q: Will the backflow preventer DOH applications be prepared by the design team?
- A: The Project Engineer will prepare the sprinkler and domestic water backflow application to the DOH.
- Q: Is see that building permit fees are waived for general building permit. Does same hold true for any fire sprinkler permit requirements?
- A: All fees for permits pulled from the City of Beacon will be waived by the City for this project. Contractors are still required to follow all other filing and approval procedures to pull their respective permits. Fees for permits from entities other than the City of Beacon will require all related permit fees to be paid by the respective contractors.
- Q: There are some inconsistencies between the drawings and the finish legend/schedule – see below:
- Room 112 is shown as RFP-1 on drawing A-800 yet is listed as EFC-1 in spec section 090600.
- Room 113 is shown as SC-1 on drawing A-800 yet is listed as RFP-1 in spec section 090600.
- Room 218 calls for EFC-5 on drawing A-801 but with WB-2. The other rooms with EFC-5 call for PT-16 (Room 109 - Unisex Toilet) and Room 121 and 122 call for WB-6. The spec finish schedule 090600 calls for WB-6 for toilet rooms and shower. Please clarify.
- A: In Room 112, the floor finish is RFP-1. See below.
- In Room 113, the floor finish is SC-1. See Below.
- In Room 218, the wall base is WB-6. See Below.
- Q: Demolition plans for the mechanical, plumbing, and electrical contracts indicate in the notes that the General Contractor is to perform all demolition. We are looking for clarification and confirmation that this applies to all plumbing and mechanical piping, equipment, fixtures, ductwork, etc. Can you please confirm that the mechanical, plumbing, and electrical contracts will not provide any demolition work?
- A: That is correct, all demo work will be by the GCC including mechanical, plumbing, and electrical piping, equipment, fixtures, ductwork, etc. The mechanical, plumbing, and electrical contracts will not provide any demolition work, with the exception of the electrical contractor de-energizing the electrical system and the electrical contractor removing the switchgear & turning it over to the Owner for storage.
- Q: Detail 10/P501 for the air compressor installation includes a concrete housekeeping pad. Is a new concrete pad required, and if so, does the plumbing contractor provide the pad?
- A: The GCC will provide all housekeeping pads for mechanical and plumbing units in mechanical rooms.
- Q: Detail 7/P501 indicates a concrete trough to be provided. Which contract provides the concrete work & grating cover?
- A: The GCC will provide the concrete work, the PC will provide the floor drain and all piping.

#### SUBSTITUTION REQUESTS

- A. None.

#### SPECIFICATIONS

- A. Section 002112
1. **ADD** Article 2, §2.1.8” “The **minimum** amount of Work the General Construction Contractor (GCC) must perform by its own forces shall be 15%.”

## B. Section 011100

1. **DELETE** paragraph 1.07.B.39 in its entirety, and **ADD** paragraph 1.07.B.39 in its place:  
“**All Prime Contractors are responsible for the coordination required with regards to wall, floor, and roof penetrations to complete their work. Cut holes are to be no more than 1/2” larger than object meant to pass through it. The GCC is responsible for performing ALL penetrations through concrete, masonry and all roof surfaces with location and size information provided by the installing Prime Contractor. Sleeves required for foundation wall utility penetrations will be provided to the GCC by the utility installing Prime Contractor. All penetrations through GWB, plywood, or similar will be performed by the installing Prime Contractor.** The GCC is responsible for installing affected finishes and shall perform all repair of finish work. If during the course of the progress construction, the GCC encounters any of the other Prime Contractors overcutting wall penetrations which require more repair than should be anticipated if performed as described above, the GCC shall notify the Architect/CM to assess the condition(s) and the Architect shall render a decision for corrective measures which will be final. All exposed finishes must be ready to receive paint, etc.; all concealed openings (piping, ductwork, conduit, etc.) must be repaired to comply with specified wall or deck conditions.”
2. **DELETE** paragraph 1.08.B.5 in its entirety. **ADD** paragraph 1.08.B.5 in its place:  
“Backfill and corresponding compaction below footings and within the interior limits of the building will be performed by the GCC. Initial backfill and corresponding compaction of the exterior of the building will be performed by the SC, inclusive of the footing drains and will be coordinated with the GCC waterproofing installation.”
3. **DELETE** paragraph 1.08.B.11 in its entirety. **ADD** paragraph 1.08.B.11 in its place:  
“Provide means as deemed necessary to provide continued concrete and masonry work throughout the Project schedule so as to complete by the Date of Substantial Completion and as recommended and permitted by the ACI 306 for Cold Weather Concreting and ACI 530.1 Section 1.8 Project Conditions.”
4. **ADD** paragraph 1.08.B.40:  
“Provide access ramps into the “building footprint” over the foundations in locations as needed, at least eight feet wide, for buggies, wheel borrows, man lifts, hi-lows, etc., before the building foundations are backfilled.”
5. **DELETE** paragraph 1.08.G.6. **ADD** paragraph 1.08.G.6:  
“Provide testing of installed system back to valves inside building per revised Note #4 on MEP201. Piping in C11A to be terminated at 4’-0” AFF and provide isolation valve for said testing.”
6. **DELETE** paragraph 1.08, H, 6. **ADD** paragraph 1.08, H, 6 in its place:  
“The SC shall include within their base bid, a fee based on a project estimate of 1,800 Cubic Yards of in place rock removal & disposal. Please see specifications 012100 & 012200 for additional information.”
7. **DELETE** paragraph 1.08, H, 7. **ADD** paragraph 1.08, H, 7 in its place:  
“Backfill and corresponding compaction below footings and within the interior limits of the building will be performed by the GCC. Initial backfill and corresponding compaction of the exterior of the building will be performed by the SC, inclusive of the footing drains and will be coordinated with the GCC waterproofing installation.”
8. **DELETE** paragraph 1.08, H, 9.
9. **DELETE** paragraph 1.10, A. **ADD** paragraph 1.10, A in its place:  
“**Sitework Contractor (SC) shall include within their Base Bid fees associated with the removal of One Thousand Eight Hundred cubic yards**



**(1,800 cy) of rock per Section 012100 Allowances. Actual field verified change in quantity, above or below this amount, will be reconciled via Unit Pricing add/deduct; See Section 012200 Unit Prices.”**

10. **DELETE** paragraph 1.15. **ADD** paragraph 1.15 in its place:

1.15 ATTACHMENTS

A. Project Milestone Schedule – as assembled by Project CM, this will be subject to change based on the actual execution of all related Prime contracts and upon review with the Prime Contractors.

B. Staging & Logistics Plan – as assembled by Project CM.

C. Beacon Rock Removal Overlay Plan – as assembled by A/E; this reference sketch depicts an overlay of the new addition exterior wall limits, the limits of the footings and the reference geotechnical boring log data and field test pit data establishing top of weathered shale for all locations and top of rock for geotechnical boring locations.

1. Bidders may utilize this overlay plan to interpolate their own estimates of likely rock removal for the project.

2. Bidders are still required to carry 1,800 cy of assumed rock removal in the Base Bid fees.

3. Weathered shale was encountered during the geotechnical boring process and is depicted and discussed in the geotechnical report boring logs. Similarly, weathered shale was observed and encountered during the excavation of the test pits shown on the reference sketch. The shale was weathered in composition and was “ripped” easily by a City DPW excavator thus not complying with the definition of “rock” in Section 312000-Earth Moving. By not qualifying as “rock” per this specification, the weathered shale material will be treated as “soil”.

D. Existing Fire Station Construction Drawings – as detailed for construction by original architect. These reference plans are for bidders’ reference for all new utility, pipe, conduit runs required for this project and how such runs may intersect with abandoned-in-place existing utility, pipe and conduit runs. Bidders are to reference these underground, under-slab and in-slab runs to calculate the necessary cuts and removals required to perform the new underground, under-slab and in-slab runs for the renovation scope.

- C. Section 074213.13

1. **ADD** the attached specification section in its entirety.

- D. Section 090600

1. **CHANGE** the floor finish in Room 112 to RFP-1.

2. **CHANGE** the floor finish in Room 113 to SC-1.

3. **CHANGE** the wall base in Room 218 to WB-6.

- E. Section 102800

1. **DELETE** paragraph 2.04, B in its entirety.

2. **ADD** paragraph 2.0401, B in its place:

B. Combination Towel Dispenser/Waste Receptacle ([T27]): Semi-recessed-mounted, stainless steel; seamless wall flanges, continuous piano hinges, tumbler locks on upper and lower doors.

1. Waste receptacle liner: Reusable, heavy-duty vinyl.

2. Towel dispenser capacity: 8 inch wide, 800 foot long rolls.

3. Waste receptacle capacity: [12] gallons.

4. Power Supply: 6-volt DC power supply.

5. Dispenser: Electronic sensor automatically dispenses towel when hands are placed under the towel opening.

6. Product: B-3979 manufactured by Bobrick.

3. **DELETE** paragraph 2.04, C in its entirety.
4. **DELETE** paragraph 2.04, E in its entirety.
5. **DELETE** paragraph 2.04, F in its entirety.
6. **DELETE** in paragraph 2.04, I, the text “(T6, T8 & T13)” and **ADD** the text “(T12, T13, & T14)”.
7. **DELETE** in paragraph 2.04, J, the text “(T9)” and **ADD** the text “(T8)”.
8. **DELETE** paragraph 2.04, K in its entirety.
9. **DELETE** paragraph 2.05, E in its entirety.

F. Section 233713

1. **ADD** the attached specification section in its entirety.

DRAWINGS

C200

1. **ADD** general note 10 to the drawing: “If there are any discrepancies between the Insite C200 drawing and the Collier LP-1 drawing, in the DOT right-of-way, the Collier LP-1 drawing shall prevail.”

LP-1

1. **ADD** general note 3 to the drawing: “If there are any discrepancies between the Insite C200 drawing and the Collier LP-1 drawing, in the DOT right-of-way, the Collier LP-1 drawing shall prevail.”

S-100:

1. See the attached sketch, S001, dated 4/3/2023, for a correction of a bottom of footing elevation.

A104

1. **ADD** a general note to the drawing: “Paint all mechanical equipment with a brick pattern.”

MEP201

1. **DELETE** note: “4” GROUND SOURCE SUPPLY & RETURN PIPING TO PUMP (P-1, 2) LOCATED IN CLOSET (C11A). RUN PIPING 5’-0” BEYOND BUILDING COORDINATE EXACT LOCATION AND DEPTH WITH SITE CONTRACTOR.”
2. **ADD** note: “4” GROUND SOURCE SUPPLY & RETURN PIPING TO PUMP (P-1, P-2) LOCATED IN CLOSET (C11A). RUN PIPING INTO CLOSET & PROVIDE ISOLATION VALVE AT 1’-6” AFF. COORDINATE EXACT LOCATION OF PIPE RISER WITH MECHANICAL CONTRACTOR & APPROVED PUMP CATALOG CUT”

M300

3. **DELETE** note: “4” GEOTHERMAL PIPING RUN 5’-0” BEYOND BUILDING. COORDINATE EXACT LOCATION AND DEPTH WITH SITE CONTRACTOR. SEE DRAWINGS (MEP200 & MEP201) FOR CONTINUATION OF PIPING.”
4. **ADD** note: “4” GEOTHERMAL PIPING BY GEOTHERMAL CONTRACTOR. MECHANICAL CONTRACTOR SHALL PICK UP PIPING FROM ISOLATION VALVE PROVIDED BY GEOTHERMAL CONTRACTOR. SEE DRAWINGS MEP200 & MEP201.”

End of Addendum #1

Project Lead:



**Budget:** Estimated: \$0.00 | Baseline: \$0.00 | **Cost:** Estimated: \$0.00 | Baseline: \$0.00 | Actual: \$0.00

WBS	Task Name	Resource Names	Start	Finish	Duration	Percent Complete	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2				
1	Pre Construction		Tue 21-Mar-23	Mon 24-Jul-23	90	0%																												
1.1	Bidding		Tue 21-Mar-23	Fri 21-Apr-23	24	0%																												
1.2	Contractors Qualification		Mon 24-Apr-23	Fri 28-Apr-23	5	0%																												
1.3	COB - Approval -Notice of Awrad		Mon 01-May-23	Mon 01-May-23	1	0%																												
1.4	Select Critical Submittals- GC		Tue 02-May-23	Mon 08-May-23	5	0%																												
1.5	Select Critical Submittals-MC		Tue 02-May-23	Mon 08-May-23	5	0%																												
1.6	Select Critical Submittals-PC		Tue 02-May-23	Mon 08-May-23	5	0%																												
1.7	Select Critical Submittals-EC		Tue 02-May-23	Mon 08-May-23	5	0%																												
1.8	Select Critical Submittals-FSC		Tue 02-May-23	Mon 08-May-23	5	0%																												
1.9	Select Critical Submittals-GTC		Tue 02-May-23	Mon 08-May-23	5	0%																												
1.10	Select Critical Submittals-SC		Tue 02-May-23	Mon 08-May-23	5	0%																												
1.11	All Other Submittals		Tue 02-May-23	Mon 24-Jul-23	60	0%																												
2	Building Work		Mon 08-May-23	Tue 06-Aug-24	327	0%																												
2.1	Mobilization		Mon 08-May-23	Tue 09-May-23	2	0%																												
2.2	Install Temp Construction Fence		Mon 08-May-23	Tue 09-May-23	2	0%																												
2.3	Building Demo		Mon 08-May-23	Fri 16-Jun-23	30	0%																												
2.4	Footings		Fri 09-Jun-23	Thu 06-Jul-23	20	0%																												
2.5	Foundation Walls		Fri 07-Jul-23	Thu 17-Aug-23	30	0%																												
2.6	Plumbers Rough In under Slab		Mon 19-Jun-23	Fri 14-Jul-23	20	0%																												
2.7	Interior Building Backfill		Mon 19-Jun-23	Fri 30-Jun-23	10	0%																												
2.8	Masonry		Fri 18-Aug-23	Thu 21-Dec-23	90	0%																												
2.9	Steel Erection		Fri 18-Aug-23	Thu 28-Sep-23	30	0%																												
2.10	Roofing		Fri 29-Sep-23	Thu 19-Oct-23	15	0%																												
2.11	Slab on grade concrete		Fri 20-Oct-23	Thu 02-Nov-23	10	0%																												
2.12	Rough Carpentry		Fri 29-Sep-23	Thu 09-Nov-23	30	0%																												
2.13	Electrical Rough In		Fri 10-Nov-23	Thu 21-Dec-23	30	0%																												
2.14	Mechanical Rough In		Fri 10-Nov-23	Thu 14-Mar-24	90	0%																												
2.15	Plumber Rough In walls		Fri 10-Nov-23	Thu 21-Dec-23	30	0%																												
2.16	Sprinkler Rough in		Fri 10-Nov-23	Thu 14-Mar-24	90	0%																												
2.17	Insulation		Fri 22-Dec-23	Thu 11-Jan-24	15	0%																												
2.18	Drywall & tapping		Fri 12-Jan-24	Thu 15-Feb-24	25	0%																												
2.19	Ceiling Gride Rough in		Fri 16-Feb-24	Thu 14-Mar-24	20	0%																												
2.20	Painting		Fri 16-Feb-24	Thu 14-Mar-24	20	0%																												
2.21	Electrical Finishes		Fri 15-Mar-24	Thu 04-Apr-24	15	0%																												
2.22	Plumbing Finishes		Fri 15-Mar-24	Thu 04-Apr-24	15	0%																												
2.23	Sprinkler Finishes		Fri 15-Mar-24	Thu 04-Apr-24	15	0%																												
2.24	Mechanical Finishes		Fri 15-Mar-24	Thu 04-Apr-24	15	0%																												
2.25	Owners equipment		Fri 05-Apr-24	Thu 09-May-24	25	0%																												
2.26	Finish Carpentry		Fri 10-May-24	Thu 13-Jun-24	25	0%																												


	Ceiling Finish's	Fri 14-Jun-24	Thu 18-Jul-24	25	0%	
2.28	Substantial completion	Fri 19-Jul-24	Fri 19-Jul-24	1	0%	
2.29	Punch list Inspection	Mon 22-Jul-24	Tue 23-Jul-24	2	0%	
2.30	Punch List work	Wed 24-Jul-24	Tue 06-Aug-24	10	0%	
3	SITE WORK	Mon 08-May-23	Tue 03-Sep-24	347	0%	
3.1	Erosions Control	Mon 08-May-23	Wed 10-May-23	3	0%	
3.2	DOT traffic Control	Mon 08-May-23	Fri 22-Dec-23	165	0%	
3.3	Building site Utilities Make safe EC,SC, GC	Fri 12-May-23	Thu 22-Jun-23	30	0%	
3.4	New addition rock removal	Fri 12-May-23	Thu 08-Jun-23	20	0%	
3.5	Excavation & Grading	Fri 09-Jun-23	Thu 13-Jul-23	25	0%	
3.6	New site Utilizes	Fri 14-Jul-23	Thu 10-Aug-23	20	0%	
3.7	Geo thermal wells	Fri 09-Jun-23	Thu 06-Jul-23	20	0%	
3.8	Site Work backfill & prep	Fri 11-Aug-23	Thu 25-Jan-24	120	0%	
3.9	Oil Separator	Fri 11-Aug-23	Thu 17-Aug-23	5	0%	
3.10	Site Concrete	Tue 14-May-24	Mon 08-Jul-24	40	0%	
3.11	Site Blacktop	Tue 09-Jul-24	Mon 22-Jul-24	10	0%	
3.12	Landscaping	Tue 14-May-24	Mon 08-Jul-24	40	0%	
3.13	Substantial completion	Fri 19-Jul-24	Fri 19-Jul-24	1	0%	
3.14	Punch list Inspection	Mon 22-Jul-24	Tue 23-Jul-24	2	0%	
3.15	Punchlist Work	Wed 24-Jul-24	Tue 06-Aug-24	10	0%	
3.16	Project Closes Outs	Wed 07-Aug-24	Tue 03-Sep-24	20	0%	



1. RED LINE IS TEMP FENCE 8' HIGH AND POST
2. STAGE AREA SITE CONTRACTOR IS RESPONSABLE OF REPAIR OF GRAVEL AREA ONCE PROJECT IS COMPLETE.








1  
A100


ROCK REMOVAL OVERLAY

SCALE: 1/8" = 1'-0" PRINT ON 24 X 36 SHT







DATE: 03/28/2023

BORING LOCATIONS			
EXISTING BORING			
NO.	SURFACE ELEVATION	T/SHALE	T/ ROCK CORE
B1	149'	-1.5'	-4.0'
B2	153'	-3.5'	-5.0'
B3	149'	-2.8'	-4.0'
B4	146'	-3.0'	-4.0'
B5	142'	-10.5'	-12.0'
B6	140'	-4.8'	-6.0'
B7	141'	-4.5'	END OF BORING at -1.0'
NEW TEST PIT			
NO.	SURFACE ELEVATION	T/SHALE	T/ ROCK CORE
T1	~ 153.61'	-3.0'	-5.0'
T2	~ 153'	-5.5'	-6.1'
T3	~ 148'	-2.0'	-3.2'
T4	~ 144'	-2.0'	-4.0'
T5	~ 142.61'	-2.1'	-3.8'
T6	~ 143.33'	-2.1'	-4.5'



FOUNDATION PLAN  
SCALE 3/8" = 1'-0"  
SCALE FOR SECTIONS 1/8" = 1'-0"




RETAINING WALL PLAN  
AT PARKING FIELD  
SCALE 1/4" = 1'-0"

- FOUNDATION NOTES**
1. All concrete for walls, footings, slabs on grade, steps etc. shall be controlled stone concrete with a minimum of 3000 PSI at 28 days. Submit preliminary design for approval before placing concrete.
  2. Reinforcing steel-standard deformed bars ASTM A615-40. Wiremesh-electric welded mesh ASTM A185.
  3. All walls and footings shall bear on undisturbed soil of 12 ton bearing capacity.
  4. Backfilling against foundation walls, subject to lateral pressures, shall not be done, unless walls are adequately braced, or until upper level floor slab has been poured.
  5. Slabs on ground shall be 6" thick, except in Apparatus Room, reinforced with mesh style 66/1010. Slab in Apparatus Room shall be 8" thick reinforced with mesh style 66/1010 top and bottom.
  6. Elevations given for bottom of footings are tentative and subject to change due to field conditions.
  7. All concrete work, details and construction shall conform to ACI 318, latest edition. Submit preliminary design for approval before placing concrete.
  8. Contractor shall set all anchor bolts, inserts, pipe sleeves and all other built-in items required by other trades before placing concrete.
  9. Abbreviations used:  
TW= top of wall  
TL= top of ledge  
EF= each face  
TF= top of pier
  10. Pin Lower Floor El. 144.42 has been assumed as (+/- 0.0). Figures given thus (+/-) are to bottom of concrete or assumed top of existing rock. Figures given thus (+) or (-) are to top of concrete.


SECTION F10  
SECTION F10A AS NOTED

TYPICAL EXPANSION JOINT



CORNER DETAIL AT COLLS  
B1-E1-A2-F3-F5

**PIER SIZES**  
P1 28"x24"x14" - 8"x8" EN  
P2 23"x22"x12" - 8"x8" EN



WILLIAM R. GIERKE  
WOODBRIDGE, N.Y.

FOR CONSTRUCTION 8-27-79

BEACON COMMUNITY DEVELOPMENT AGENCY  
100 WOLCOTT AVENUE  
BEACON, NEW YORK

BEACON FIREHOUSE IMPROVEMENTS

TOMPKINS HOSE COMPANY  
PROJECT NO. B77-HS-36-0101


**FOUNDATION PLAN**

the office of ira kessler architect  
432 MAIN ST., BEACON, N.Y. 12506 (914) 891-7016

DRAWING NUMBER  
**S-1**

SCALE: AS SHOWN PROJECT NO. 7702-C DRAWN BY: DATE: JUNE 1, 1979







**UPPER LEVEL FRAMING PLAN**  
FIN FLOOR EL 158.33 ASSUMED (+0.0)  
ELEVATIONS GIVEN THUS (-) ARE TO TOP  
OF STEEL FROM FIN FLOOR EL 158.33

**SLAB REINFORCEMENT**  
51 - 6" SLAB - 5" - 6" C. R. T. - 1" - 6" C. TOP  
TEMP. STEEL #4 @ 12" O.C.  
50 - 4" SLAB - 1" - 8" C. R. T. - 1" - 8" C. TOP  
TEMP. STEEL #3 @ 12" O.C.


**TRUSS LINTELS**  
L1 - 2L - 5" x 8" x 1/2" - N.D. PLUS 1" D  
PROVIDE 2L - 3" x 3" x 1/4" FOR OTHER OPENINGS - M.O. + 10

	A2	A4	A7	A8	A9	B1	B2	B4	B6	B9	C1	C2	C6	C9	D2	D6	D9	E1	E2	E4	E6	F2	F3	F5	EFG
HIGH ROOF TOP OF JOISTS EL 176.31																									
LOW ROOF TOP OF JOISTS EL 169.38																									
FIN FLOOR EL 158.33 ASSUMED (+0.0)																									
FIN FLOOR EL 144.42																									
BASEPLATES 1" DIMENSIONS H - 5"	10x1x10		7x1x13	7x1x13	13x1x7	10x1x10	7x1x12	10x1x11	10x1x10	10x1x17	12x1x10	12x1x10	15x1x14	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17	15x1x17




**HIGH & LOW ROOF FRAMING PLAN**  
LOW ROOF - TOP OF JOISTS (+11'10")  
HIGH ROOF - TOP OF JOISTS (+16'10")  
ALL STEEL SUPPORTING JOISTS TO BE  
C-26) BELOW TOP OF JOISTS


NOTE: DIMENSIONS OMITTED AND MARKS AT THIS  
ARE TO BE COORDINATED WITH MECHANICAL  
APPROVED EQUIPMENT DRAWINGS



**Typical Column Base Detail**



**Typical Floor Construction**




**SECTION X-X**

**EQUIPMENT ENCLOSURE**


- STRUCTURAL STEEL NOTES:**
- All structural steel shall conform to ASTM A36. Fabricator of steel shall submit affidavit showing compliance of the steel with the above requirements.
  - Design, fabrication and erection shall conform to the "Manual of Steel Construction" AISC, latest edition.
  - Shop connections, and field connections within 3 feet of columns shall be welded riveted or HS bolts. (A325).
  - Rivets and bolts shall be 3/4 inch.
  - Contractor shall submit checked anchor-bolt plans, erection drawings and shop details for approval before starting work. Contractor shall verify location of anchorbolts and other pertinent dimensions at site.
  - Provide milled stiffeners under offset columns and for girders over top of columns.
  - All concrete shall be controlled stone concrete with a minimum of 3000 PSI in 28 days
  - Reinforcing steel- standard deformed bars ASTM A615-40. Wiremesh shall be electric welded mesh conforming to ASTM A185 and ASTM A82.

FOR CONSTRUCTION 8/27/79	
1. ADDENDUM NO. 1	6/27/79
2. DESCRIPTION	DATE
REVISIONS	
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK	
BEACON FIREHOUSE IMPROVEMENTS	
TOMPKINS HOSE COMPANY PROJECT NO. BT-15-36-0101	
UPPER TIER & ROOF FRAMING PLANS	
the office of ira kessler architect 432 MAIN ST. BEACON, N.Y. 12508 (914) 851-7016	
SCALE: AS SHOWN	PROJECT NO. T702-G
DRAWN BY	DATE: JUNE 1, 1979




5.2






FOR CONSTRUCTION		8-27-79
NO.	DESCRIPTION	DATE
REVISIONS		
BEACON COMMUNITY DEVELOPMENT AGENCY		
100 WOLCOTT AVENUE BEACON, NEW YORK		
BEACON FIRE HOSE IMPROVEMENTS		
TOMPKINS HOSE COMPANY		
PROJECT NO. 877-HS-01A-010		
DETAILS		
the office of ira kessler architect		DRAWING NUMBER
492 NASSAU ST. BEACON, N.Y. 12508 (914) 831-7070		5.3
SCALE: AS SHOWN	PROJECT NO. 7702-10	DATE: JUNE 1979





KEY:  
BROWN SAND, TOP SOIL, & BROKEN ROCK  
CORED ROCK, BLACK SANDSTONE, & SHALE


BORING DATA PREPARED BY:  
ATLANTIC DRILLING INC.  
1020 SAWMILL ROAD, YONKERS, N.Y. 10710  
TEL: 914-968-1121



LIST OF DRAWINGS

Number	Drawings Title
A-1	Site Plan
A-2	Lower Level Plan
A-3	Upper Level Plan
A-4	Roof Plan & Details
A-5	Elevations
A-6	Section
A-7	Wall Sections
A-8	Reflected Ceiling Plans
A-9	Stair Details & Miscellaneous Details
A-10	Schedules and Details
S-1	Foundation Plan & Details
S-2	Upper Floor Framing, Roof Framing
S-3	Details
HVAC-1	Lower Level Plan
HVAC-2	Upper Level Plan
P-1	Site Plan
P-2	Lower Level Plan
P-3	Upper Level Plan
E-1	Site Plan
E-2	Lower Level Plan - Power
E-3	Upper Level Plan - Power
E-4	Lower Level Plan - Lighting
E-5	Upper Level Plan - Lighting
E-6	Lower Level Plan - Communications
E-7	Upper Level Plan - Communications
E-8	Schedules & Riser Diagrams

LEGEND & SYMBOLS



ABBREVIATIONS

T.C.	TOP OF CURB
T.W.	TOP OF WALL
B.C.	BOTTOM OF CURB
GYP. BD.	GYPSUM BOARD
V.A.T.	VINYL ASBESTOS TILE
C.G.	CERAMIC
ALUM.	ALUMINUM
MTL.	METAL
H.M.	HOLLOW METAL
Y.D.	YARD DRAIN
R.D.	ROOF DRAIN
D.F.	DRINKING FOUNTAIN


DRWG  
A-1




NO.	DESCRIPTION	REVISIONS	BY	DATE
-----	-------------	-----------	----	------

SIDEWALK RAMP TYPE 3 - NOT TO SCALE

RAMP CONSTRUCTION IN ACCORDANCE W/  
"BARRIER FREE DESIGN: THE LAW" VOL. 1,  
1971 BY EASTERN INDEPENDENT VETERANS ASSOC.  
N.Y.C. 10016 (LAW OF N.Y. 1975 CHAP. 245).

CURB DETAIL - 1" = 1'-0"





SCHEMATIC PLAN  
OF BASE B.D. - LOWER LEVEL  
NO SCALE



ROOM SLAB ONLY  
IN AREAS SHOWN

ONLY PARTITIONS & EXTERIOR WALL  
SHOWN ARE INCLUDED.

FOR CONSTRUCTION 8-27-79

RECONSTRUCTION DEVELOPMENT AGENCY 37 WOODSTOCK AVENUE NEW YORK, N.Y. 10017			
DESIGN AND CONSULTING SERVICES TERRY KESSLER ARCHITECT PROJECT NO. 877-45-36-0-01 LOWER LEVEL PLAN			
the office of ira kessler architect 432 Main St. Beacon, N.Y. 12508 (914) 831-7090			DRAWING NUMBER A-2
SCALE: 1/8" = 1'-0"	PROJECT NO. 877-45-36-0-01	DRAWN BY: R.S.	DATE: 8-27-79





FOR CONSTRUCTION		6-27-79
1	APPENDIX No. 1	6-27-79
NR	DESCRIPTION	DATE
REVISIONS		
BEACON COMMUNITY DEVELOPMENT AGENCY 60 NO. COTT AVENUE BEACON, NEW YORK <b>BEACON FIREHOUSE IMPROVEMENTS</b> <b>TOMPKINS HOSE COMPANY</b> PROJECT NO. 277-145-35-0101 UPPER LEVEL PLAN		
<b>the office of ira kessler architect</b> 432 Main St. Beacon, NY 12508 (914) 831-7096		DRAWING NUMBER <b>A-3</b>
SCALE	PROJECT NO. 77020	DATE JUNE 1, 1979



TYP. ROOF VENT DETAIL  
SCALE: 1/2" = 1'-0"

TYP. ROOF DRAIN DETAIL  
SCALE: 1/2" = 1'-0"

PITCH POCKET DETAIL  
SCALE:  $1\frac{1}{2}" = 1'-0"$


A/C CURB DETAIL  
SCALE:  $1\frac{1}{2}" = 1'-0"$

TYP. SECTION THRU ROOF SCREEN  
SCALE 1 1/2" = 1'-0"

ROOF HATCH DETAIL  
SCALE 1 1/2" = 1'-0"

SKYLIGHT DETAIL  
SCALE 1/2" = 1'-0"

ROOF PLAN



FOR CONSTRUCTION 8-27-79

ADDENDUM NO. 1 6-27-79

DATE	DESCRIPTION	DATE
	REVISIONS	

BEACON COMMUNITY DEVELOPMENT AGENCY  
100 WOLCOTT AVENUE BEACON, NEW YORK

BEACON FIREHOUSE IMPROVEMENTS

TOMPKINS HOSE COMPANY  
PROJECT NO: B77-H5-36-0101  
ROOF PLAN & DETAILS








**the office of ira kessler architect**  
432 MAIN ST. BEACON, NY 12508 (914)-831-7096

DRAWING NUMBER
----------------

A. 4

SCALE 3/4" = 1'-0"	PROJECT NO 7702-C	DRAWN BY	DATE JUNE 1, 1979
--------------------	-------------------	----------	-------------------






FOR CONSTRUCTION		8-27-79
N2	DESCRIPTION	DATE
REVISIONS		
SEACON COMMUNITY DEVELOPMENT AGENCY 100 WILCOTT AVENUE SEACON, NEW YORK		
SEACON FIREHOUSE IMPROVEMENTS		
TOMPKINS HOSE COMPANY PROJECT NO. BT-100-30-0101 BUILDING ELEVATIONS		
the office of ira kessler architect 432 MAIN ST., SEACON, N.Y. 12508 (518) 851-7316		DRAWING NUMBER A-5
SCALE: 3/4"=1'-0"	PROJECT NO. 7702-C	DRAWN BY
		DATE: JUNE 1, 1979








SECTION 1

SECTION 2

SECTION 3

SECTION 4




SECTION A-A  
SCALE 1/8"=1'-0"


FOR CONSTRUCTION 2-27-79	
ADDENDUM NO.	DATE
REVISIONS	DATE
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK	
BEACON FIREHOUSE IMPROVEMENTS	
TOMPKINS HOSE COMPANY PROJECT NO. BTTH-193-0101	
WALL SECTIONS	
the office of ira kessler architect 432 N. MAIN ST., BEACON, N.Y. 10508 (914) 851-7010	DRAWING NUMBER A-7
SCALE 3/4"=1'-0"	PROJECT NO. 7702-C
DRAWN BY	DATE JUNE 1, 1979








UPPER LEVEL  
REFLECTED CEILING PLAN



LOWER LEVEL  
REFLECTED CEILING PLAN




WEST ELEVATION OF GALLEY  
KITCHEN & GALLEY DETAILS

EAST ELEVATION  
SCALE 1/8" = 1'-0"







NORTH ELEVATION  
SOUTH ELEVATION, WITHOUT SINK & DISHWASHER

WEST ELEVATION



FOR CONSTRUCTION 8.27.79		
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK		
BEACON FIREHOUSE IMPROVEMENTS		
TOMPKINS HOSE COMPANY PROJECT NO. BT-HS-30-D101 REFLECTED CEILING PLANS		
the office of ira kessler architect 452 MAIN ST. BEACON, N.Y. 12508 (914) 831-7036	DRAWING NUMBER A-8	DATE JUNE 1, 1979
SCALE 1/8" = 1'-0"	PROJECT NO. 7702-C	DRAWN BY





FOR CONSTRUCTION 8-27-79

△	ADDENDUM №1	6.27.79
№	DESCRIPTION	DATE
REVISIONS		
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK		
BEACON FIREHOUSE IMPROVEMENTS TOMPKINS HOSE COMPANY PROJECT № B77-H4-36-0101 STAIR AND MISC. DETAILS		
the office of ira kessler architect 432 MAIN ST; BEACON, N.Y. 12508 (914)-891-7096		DRAWING NUMBER A.9
SCALE AS NOTED	PROJECT NO 7702-C	DRAWN BY
		DATE JUNE 1, 1979




# DOOR SCHEDULE


DOOR NO.	TYPE	MATERIAL	SIZE	BUCK TYPE	SADDLE TYPE	REMARKS	LRDN. SET
1	A	GLASS & ALUMINUM	5'-4" x 7'-0" x 1 3/4"	A	ALUM.	ALT. NO. 2	BY MFR.
2	A	GLASS & ALUMINUM	5'-4" x 7'-0" x 1 3/4"	A	ALUM.	ALT. NO. 2	BY MFR.
3	B	H.M.	2'-6" x 7'-0" x 1 3/4"	B	H.M.	ALT. NO. 2	4
4	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	MARBLE ALT. NO. 2	4
5	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	MARBLE ALT. NO. 2	2
6	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	MARBLE ALT. NO. 2	2
7	D	H.M.	6'-0" x 7'-0" x 1 3/4"	B	H.M.	ALT. NO. 2	7
8	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALT. NO. 2	4
9	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALT. NO. 2	4
10	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALT. NO. 2	4
11	D	H.M.	4'-10" x 7'-0" x 1 3/4"	S	H.M.	ALUM.	8
12	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALT. NO. 2	5
13	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALT. NO. 2	5
14	E	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	C	H.M.	ALUM. ALT. NO. 2	9
15	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALUM.	1
16	D	H.M.	5'-0" x 7'-0" x 1 3/4"	B	H.M.	ALUM.	6
17	D	H.M.	5'-0" x 7'-0" x 1 3/4"	B	H.M.	ALUM.	6
18							
19							
20							
21	F	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	A	H.M.	FIXED H.M. PANEL ABOVE	1
22	F	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.		5
23	F	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.		5
24	F	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.		5
25	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.		4
26	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	MARBLE	2
27	F	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.		5
28	G	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALUM.	1
29	G	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.	SEE DETAILS DWG. A-B	1
30	G	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.	SEE DETAILS DWG. A-B	1
31	G	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.		1
32	G	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALUM.	1
33	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.		1
34	C	H.M.	2'-6" x 7'-0" x 1 3/4"	B	H.M.	MARBLE	3
35	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALUM.	4
36	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.		1
37	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	H.M.		1
38	F	H.M. & GLASS	3'-0" x 7'-0" x 1 3/4"	B	H.M.	ALUM.	1
39	H	WOOD & GLASS	14'-0" x 14'-8" x 1 3/4"	D	STEEL		-
40	H	WOOD & GLASS	14'-0" x 14'-8" x 1 3/4"	D	STEEL		-
41	H	WOOD & GLASS	14'-0" x 14'-8" x 1 3/4"	D	STEEL		-
42	C	H.M.	3'-0" x 7'-0" x 1 3/4"	B	STEEL		-

# FINISH SCHEDULE


ROOM NO.	ROOM NAME	FLOOR	BASE	WALLS				CEILING		REMARKS
				N	S	E	W	HT.	FINISH	
L-1	KITCHEN	QUARRY TILE	QUARRY TILE	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	8'-0"	MT. MASONRY TILE	ALTERNATES NOS. 1, 2, 3, 4, 7, 8 APPLY
L-2	STAIR	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	-	-	ALTS. NOS. 1, 2, 4, 7 APPLY
L-3	VESTIBULE	CONC.	-	GYP. BD.	GYP. BD.	CONC.	GYP. BD.	-	-	ALT. NO. 4 APPLIES
L-4	EQUIPMENT	CONC.	-	GYP. BD.	GYP. BD.	CONC.	GYP. BD.	-	-	ALT. NO. 4 APPLIES
L-5	AIR CONDITIONING EQUIPMENT ROOM	CONC.	-	GYP. BD.	GYP. BD.	CONC.	GYP. BD.	-	-	ALT. NO. 4 APPLIES
L-6	STORAGE	V.A.T.	VINYL	GYP. BD.	GYP. BD.	CONC.	GYP. BD.	9'-0"	GYP. BD.	ALTS. NOS. 1, 2, 3, 4, 7 APPLY
L-7	MEETING ROOM	V.A.T.	VINYL	GYP. BD.	GYP. BD.	CONC.	GYP. BD.	-	ACOUS. TILE	ALTS. NOS. 1, 2, 3, 4, 7 APPLY
L-8	MENS ROOM	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	9'-0"	GYP. BD.	ALTS. NOS. 1, 2, 3, 4, 5, 9 APPLY
L-9	WOMENS ROOM	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	9'-0"	GYP. BD.	ALTS. NOS. 1, 2, 3, 4, 5, 9 APPLY
L-10	JANITORS CLOSET	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	9'-0"	GYP. BD.	ALTS. NOS. 1, 2, 3, 4, 5, 9 APPLY
L-11	COAT ROOM	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	ALTS. NOS. 1, 2, 3, 4, 6, 7 APPLY
L-12	LOBBY	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	ALTS. NOS. 1, 2, 3, 4, 6, 7 APPLY
L-13	VESTIBULE	V.A.T.	VINYL	GYP. BD.	GYP. BD.	ALUM. & GLASS	ALUM. & GLASS	9'-0"	ACOUS. TILE	ALTS. NOS. 1, 2, 3, 4, 6, 7 APPLY
U-1	APPARATUS	CONC. *	-	CONC. BLOCK	CONC. BLOCK	CONC. BLOCK	CONC. BLOCK	-	-	*SPECIAL FLR. FINISH; SEE SPECIFICATIONS.
U-2	STORAGE	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	GYP. BD.	
U-3	STAIR	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	-	GYP. BD.	
U-4	ENTRY	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	
U-5	REAR ROOM	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	
U-6	MENS TOILET	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	9'-0"	WATERPROOF GYP. BD.	
U-7	GALE	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	GYP. BD.	
U-8	OFFICE	V.A.T.	VINYL	GYP. BD.	NETL. & GLASS	CONC. BLOCK	GYP. BD.	9'-0"	ACOUS. TILE	
U-9	OFFICE	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	
U-10	CREATOR	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	
U-11	JANITORS CLOSET	V.A.T.	VINYL	WATERPROOF GYP. BD.	WATERPROOF GYP. BD.	WATERPROOF GYP. BD.	WATERPROOF GYP. BD.	8'-0"	GYP. BD.	
U-12	BATH	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	CER. TILE	8'-0"	GYP. BD.	
U-13	COMMUNICATIONS ROOM	V.A.T.	VINYL	METAL & GLASS	CONC. BLOCK	METAL & GLASS	GYP. BD.	9'-0"	ACOUS. TILE	
U-14	TRUSTEES ROOM	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	
U-15	DRIVERS ROOM	V.A.T.	VINYL	GYP. BD.	GYP. BD.	GYP. BD.	GYP. BD.	9'-0"	ACOUS. TILE	
U-16	UNIFORM STORAGE	V.A.T.	VINYL	CEDAR PLY PANEL	CEDAR PLY PANEL	CEDAR PLY PANEL	CEDAR PLY PANEL	9'-0"	GYP. BD.	




TYPICAL HEAD DETAIL @ OVERHEAD DOOR




TYPICAL JAMB DETAIL @ OVERHEAD DOOR



TYP. HEAD & JAMB DETAIL @ EXTERIOR STL. STUD WALL



TYP. SILL DETAIL @ EXTERIOR STL. STUD WALL



TYP. SILL DETAIL @ EXT. MASONRY WALL


FOR CONSTRUCTION 8.27.79

BEACON COMMUNITY DEVELOPMENT AGENCY  
100 WILCOTT AVENUE  
BEACON, NEW YORK

BEACON FIREHOUSE IMPROVEMENTS

TOMPKINS HOSE COMPANY  
PROJECT NO. BTI-HS-36-001  
SCHEDULES & INTERIOR ELEVATIONS



the office of ira kessler architect  
492 MAIN ST., BEACON, N.Y. 12508 (914) 831-7096



A-10

SCALE AS NOTED PROJECT NO. T702-C DRAWN BY DATE JUNE 1, 1979








MINIMUM FIXTURE CONNECTION SCHEDULE						
FIXTURE	SOIL	WASTE	VENT	H.W.	C.W.	V.B.
WATER CLOSET	4"	2"	2"	1/2"	1/2"	—
URINAL	—	2"	1/2"	—	1"	YES
LAVATORY	—	1 1/2"	1 1/2"	1/2"	1/2"	—
MOP SINK	—	3"	1 1/2"	3/4"	3/4"	YES
SINK	—	2"	1 1/2"	1/2"	1/2"	—
SHOWER	—	2"	1 1/2"	1/2"	1/2"	—
ELECTRIC WATER COOLER	—	1 1/2"	1 1/2"	—	1/2"	—

#### SYMBOLS

—	SOIL OR WASTE PIPING BELOW FLOOR
—	VENT PIPING
—	SOIL OR WASTE PIPING ABOVE FLOOR
—	COLD WATER PIPING
—	HOT WATER PIPING
G	GAS PIPING
SD	STORM DRAINAGE PIPING
V	VENT
S	SOIL
W.S.	WATER SERVICE
C.W.	COLD WATER
H.W.	HOT WATER
C.O.	CLEAN OUT
C.O.D.P.	CLEAN OUT DECK PLATE
R.D.	ROOF DRAIN
E.W.C.	ELECTRIC WATER COOLER
V.T.R.	VENT THRU ROOF
W.C.	WATER CLOSET
LAV.	LAVATORY
UR.	URINAL
M.S.	MOP SINK
S.H.	SHOWER
D.V.	DRAIN VALVE
F.A.I.	FRESH AIR INTAKE
W.H.	WALL HYDRANT
□	SQUARE FEET
⊕	DESIGNATES SOIL OR WASTE STACK
P.R.V.	PRESSURE REDUCING VALVE
A.F.F.	ABOVE FINISHED FLOOR
F.D.	FLOOR DRAIN
T. & P.	TEMPERATURE & PRESSURE
C.B.	CATCH BASIN
H.B.	HOSE BIBB - 1" & 1/2" A.F.F.
LDR.	LEADER
H.C.	HUNG CEILING
V.M.	VENDING MACHINES
S.S.	SANITARY SEWER
N.	WASTE
F.F.D.	FUNNEL FLOOR DRAIN
A.F.	ABOVE FLOOR
B.F.	BELOW FLOOR
D.W.	DISHWASHER
I.M.	ICE MAKER





PLAN - LOWER LEVEL

FOR CONTINUATION OF  
STORM DRAIN, GAS, WATER  
& SANITARY SEWER PIPING,  
SEE DWG. # P-1, SITE PLAN

FOR CONSTRUCTION	
ADDENDUM #1 6-27-79	
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK	
BEACON FIREHOUSE IMPROVEMENTS	
TOMPKINS HOSE COMPANY	
LOWER LEVEL PLAN	
the office of ira kessler architect 432 Main St. Beacon, N.Y. 12508 (914) 831-7090	DRAWING NUMBER <b>P-2</b>
SCALE 1/8" = 1'-0"	PROJECT NO. 7702C DRAWING PG. DATE 6-1-79





FOR CONSTRUCTION

ADDENDUM #1 6-27-79

BEACON COMMUNITY DEVELOPMENT AGENCY  
100 WOLCOTT AVENUE  
BEACON, NEW YORK

BEACON FIREHOUSE IMPROVEMENTS

TOMPKINS HOSE COMPANY  
UPPER LEVEL PLAN

the office of ira kessler architect  
432 Main St. Beacon, N.Y. 12508 (914) 831-7090


DRAWING NUMBER  
**P-3**

SCALE: 1/8" = 1'-0"  
PROJECT NO. 7702C  
DRAWN BY: R.G.  
DATE: 6-1-79

SYMBOL LIST	
	FLUORESCENT LIGHT FIXTURE/CEILING WALL MOUNTED
	INCANDESCENT LIGHT FIXTURE/CEILING WALL MOUNTED
	EXIT LIGHT FIXTURE/CEILING WALL MOUNTED
	SINGLE POLE SWITCH
	3 WAY SWITCH
	4 WAY SWITCH
	MOMENTARY CONTACT SWITCH
	DIMMER SWITCH
	KEY OPERATED REMOTE MOTOR STARTER SWITCH
	COMBINATION DISCONNECT SWITCH & MAGNETIC ACROSS THE LINE STARTER
	MAGNETIC STARTER
	DISCONNECT SWITCH UNFUSED UNLESS OTHERWISE NOTED
	EMERGENCY BREAKGLASS EQUIPMENT SHUTDOWN SWITCH
	MOTOR - NO INDICATES HORSEPOWER
	WALL MOUNTED CABINET HEATER
	DUPLEX RECEPTACLE
	DUPLEX RECEPTACLE GROUND FAULT INTERRUPTER TYPE
	FLOOR MOUNTED RECEPTACLE AMPS, POLES, TO MATCH EQUIPMENT FURNISHED BY OWNER.
	CONDUIT RUN CONCEALED IN CEILING OF FLOOR BELOW OR IN FLOOR SLAB
	CONDUIT RUN CONCEALED IN CEILING AND WALLS
	CONDUIT HOMERUN - NO OF ARROWS INDICATES CIRCUITS.
	PHONE OUTLET (F) FIRE; (P) POLICE (H) HOUSE (J) JACK
	FIRE PHONE BELL
	FIRE PHONE MONITOR
	FIRE PHONE HORN
	MIKE OUTLET
	INTERCOM MASTER
	WARNING LIGHT (PLECTRON)
	INTERCOM SPEAKER



#### ABBREVIATIONS

AFF	- ABOVE FINISHED FLOOR
CO	- CONDUIT ONLY
CS	- CABLE SUPPORT BOX
EC	- EMPTY CONDUIT
EM	- EMERGENCY DEVICE
EW	- ELECTRIC WATER COOLER
FOO	- FURNISHED BY OTHERS
NIC	- NOT IN CONTRACT (ELECTRIC, UNLESS NOTED OTHERWISE)
VT	- VAPORTIGHT
WP	- WEATHERPROOF
XP	- EXPLOSION PROOF



FOR CONSTRUCTION

APPENDUM #1 6-27-79	
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK	
BEACON FIREHOUSE IMPROVEMENTS TOMPKINS HOSE COMPANY	
SITE PLAN	
the office of ira kessler architect 452 MAIN ST. BEACON, N.Y. 12508 (914) 833-7076	DRAWING NUMBER E-1
SCALE 1" = 2'-0"	PROJECT NO. 7702C DRAWN BY S.Z. DATE 6-1-79




FOR CONSTRUCTION			
ADDENDUM #1 6-27-79			
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK			
BEACON FIREHOUSE IMPROVEMENTS			
TOMPKINS HOSE COMPANY			
LOWER LEVEL PLAN - POWER			
the office of ira kessler architect 432 MAIN ST. BEACON, N.Y. 12508 (914) 831-7096			DRAWING NUMBER
			E-2
SCALE 1/8" = 1'-0"	PROJECT NO. 7702 C	DRAWN BY S.Z.	DATE 6-1-79



NOTES.

1. Connect to Motorized Shutter.
2. Remote Start-Stop switch with pilot light. Interconnect both Apparatus Room exhaust fans to be activated from this switch.
3. Interconnect H&V unit to automatically start when Apparatus Fans are activated. H&V shall also be wired to start from respective starter.
4. All receptacles located in Apparatus Room shall be GFI Type. Receptacles located in Surface Trough on rear wall shall be protected by GFI circuit breaker.
5. All electrical equipment located in Apparatus Room shall be mounted 4'-0" AFF min.



FOR CONSTRUCTION

ADDENDUM #1 6-27-79

BEACON COMMUNITY DEVELOPMENT AGENCY  
100 WOLCOTT AVENUE BEACON, NEW YORK

## BEACON FIREHOUSE IMPROVEMENTS

TOMPKINS HOSE COMPANY  
UPPER LEVEL PLAN - POWER

**the office of ira kessler architect**  
432 MAIN ST. BEACON, N.Y. 12508 (914) 831-7096


DRAWING NUMBER
----------------


E-3


SCALE $\frac{1}{8}" = 1' - 0"$	PROJECT NO. 7702C	DRAWN BY S.Z.	DATE 6-1-79
--------------------------------	-------------------	---------------	-------------










 APPENDUM #1 6-27-79	
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK	
BEACON FIREHOUSE IMPROVEMENTS	
TOMPKINS HOSE COMPANY UPPER LEVEL PLAN - LIGHTING	
the office of ira kessler architect 432 Main St. Beacon, N.Y. 12508 (914) 831-7090	DRAWING NUMBER E-5
SCALE 1/8" = 1'-0"	PROJECT NO. 7702 C DRAWN BY S. Z. DATE 6-1-79



PLAN - LOWER LEVEL  
COMMUNICATIONS



FOR CONSTRUCTION			
APPENDUM #1 6-27-79			
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK			
BEACON FIREHOUSE IMPROVEMENTS TOMPKINS HOSE COMPANY LOWER LEVEL-COMMUNICATIONS			
the office of ira kessler architect 432 Main St. Beacon, N.Y. 12508 (914) 831-7090			DRAWING NUMBER <b>E-6</b>
SCALE 1/8" = 1'-0"	PROJECT NO 7702 C	DRAWN BY S.Z.	DATE 6-1-79




COMMUNICATIONS  
ROOM PART PLAN  
SCALE: 1/4" = 1'-0"

PLAN-UPPER LEVEL  
COMMUNICATIONS

FOR CONSTRUCTION			
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK			
BEACON FIREHOUSE IMPROVEMENTS			
TOMPKINS HOSE COMPANY			
UPPER LEVEL-COMMUNICATIONS			
the office of ira kessler architect 432 MADISON ST. - ARDEN, N.Y. 12508 (914) 831-7096			DRAWING NUMBER <b>E-7</b>
SCALE: 1/8" = 1'-0"	PROJECT NO. 7702-C	DRAWN BY: S.Z.	DATE: 6-1-79





PANEL	CIRCUITS	FRAME	TRIP	POLES	SERVICES	WIRE	COMP.
A	3-20, 22-24	100	20	1	ACTIVE	#12	NO REQ'D
	2-23, 25-28	100	20	1	SPARE	-	-
	29, 30	-	-	1	SPARE	-	-
	1	100	30	1	DIMMER	2#10	1/2"
B	1-26	100	20	1	ACTIVE	#12	NO REQ'D
	27-33	100	20	1	SPARE	-	-
	34	100	60	3	PANEL C	4#6	1"
C	1-6	100	20	1	ACTIVE	#12	NO REQ'D
	7, 8, 9	100	20	1	ACTIVE	#12	-
	10-12	-	-	1	SPARE	-	-
EA	1-6	100	20	1	ACTIVE	#12	NO REQ'D
	7-12	100	15	1	CIRC. PUMPS	2#12 1#14g	NO REQ'D
	13	100	20	1	TELEPHONE RECEPTACLE	#12	AS REQ'D
EB	1-12	100	20	1	ACTIVE	#12	NO REQ'D
	13-18	100	20	1	SPARE	-	-

Branch Circuit		Conductor		Conduit		Remarks
Ckt No	Circuit Breaker	Load Designation	KW HP	No	Size	
1	3 200	MEETING ROOM FAN	5	3/4	1 1/2"	
2	3 70	COMM. RM. FAN	4/5	4/1	1"	
3	3 100	READY RM. FAN	3/4	4/1	1 1/4"	
4	3 20	APPL. ROOM FAN	2	3/4	1 1/2"	
5	3 15	EXHAUST	1 1/4	1/2		
6	3 15	EXHAUST	1 1/4	1/2		
7	3 15	EXHAUST	1 1/4	1/2		
8	3 15	EXHAUST	1 1/4	1/2		
9	3 15	EXHAUST	1 1/4	1/2		
10	3 20	DRIVER	1	3/4		
11	3 20	OVERHEAD DOOR MOTOR	2	3/4		
12	3 20	SPARE	-	-		
13	3 20	OVERHEAD DOOR MOTOR	2	3/4		
14	1 15	DUPLEX RECEPTACLE	1/2	1/2		
15	1 15	RECEPTACLE	1/2	1/2		
16	3 60	HOSE WASH	6	3/4	1	
17	3 20	SPARE	-	-		
18	3 20	SPARE	-	-		
19	3 20	SPARE	-	-		
20	3 20	SPARE	-	-		

Branch Circuit		Conductor		Conduit		Remarks
Ckt No	Circuit Breaker	Load Designation	KW HP	No	Size	
1	3 70	GREEN MOTOR THROUGH F	10	3/4	1 1/2"	
2	2 20	HOT PLATE	5	3/4	1 1/2"	
3	2 20	DRIVE CH. FAN	1	3/4	1 1/2"	
4	2 30	AIR COND.	1 1/2	3/4	1 1/2"	
5	1 20	BATTERY CHARGER	1/2	2/1	12	
6	1 20	BATTERY CHARGER	1/2	2/1	12	
7	3 60	DRIVE CH. FAN	1	3/4	1 1/2"	
8	2 10	SPARE	-	-		
9	2 20	OVERHEAD DOOR MOTOR	2	3/1	12/12g	
10	2 20	SPARE	-	-		

FOR CONSTRUCTION

ADDENDUM #1 6-27-79

BEACON COMMUNITY DEVELOPMENT AGENCY  
100 WOLCOTT AVENUE  
BEACON, NEW YORK

BEACON FIREHOUSE IMPROVEMENTS

TOMPKINS HOSE COMPANY  
SCHEDULES & RISER DIAGRAMS


the office of ira kessler architect  
432 MAIN ST. BEACON, N.Y. 12508 (914) 831-7076

DRAWING NUMBER  
E-8

SCALE NONE PROJECT NO 7702C DRAWN BY G.Z. DATE 6-1-79

# SYMBOLS


- SUPPLY DUCT
- RETURN OR EXHAUST DUCT
- F.T.R. FIN-TUBE RADIATION
- F.R.C. FULLY RECESSED CONVECTOR
- S.R.C. SEMI-RECESSED CONVECTOR
- T.W.U. THRU-WALL UNIT
- C.H. CABINET HEATER
- C.R. CEILING REGISTER
- T.R. TOP REGISTER
- B.R. BOTTOM REGISTER
- ( ) FIGURES IN BRACKETS INDICATE CFM
- P.C. PLUMBING CONTRACTOR
- C.D. CEILING DIFFUSER
- G.C. GENERAL CONTRACTOR
- M.D. MOTORIZED DAMPER
- O.A.I. OUTSIDE AIR INTAKE
- H.W.S. HOT WATER SUPPLY
- H.W.R. HOT WATER RETURN
- M.B.H. THOUSANDS OF BTU PER HOUR
- H.C. HUNG CEILING
- S.E.F. SMOKE EXHAUST FAN
- H.V.A.C. HEATING VENTILATING & AIR CONDITIONING CONTRACTOR
- F.C. FLEXIBLE CONNECTION
- A.D. ACCESS DOOR
- T.R.F. THRU-ROOF
- ⊕ BREATHING OPENING BY G.C. (FREE AREA GIVEN IN SQ. FT.) ABOVE H.C.
- ⊖ THERMOSTAT
- ⊕ LOUVERED OR UNDERCUT DOOR BY G.C. (FREE AREA GIVEN IN SQUARE INCHES)
- E.F. EXHAUST FAN
- ⊕ THRU BEAM
- K.E. KITCHEN EXHAUST
- DIRECTION OF FLOW
- ⊕ SOUND INSULATED
- ⊕ FIRE DAMPER
- B.B.R. BASE BOARD RADIATOR
- B.D. BAROMETRIC DAMPER
- T.C. TERRA COTTA



## THRU-WALL - AIR-CONDITIONING UNIT PIPING CONNECTIONS

NO SCALE  
PERFORMANCE DATA  
TYPE K-10 - COOLING BTUH - 8,000 - HOT WATER HEATING BTUH - 12,500 CFM @ 1050 RPM - 270  
TYPE K-12 - COOLING BTUH - 11,700 - HOT WATER HEATING BTUH - 13,300 CFM @ 1050 RPM - 320

EACH UNIT SHALL HAVE A STANDARD FLUSH - TYPE EXTRUDED ALUMINUM LOUVER W/PERIMETER FRAME



## BOILER PIPING DIAGRAM

NO SCALE


### CIRCULATORS

LOBBY ZONE - B & G - 100-115 - 1/4 HP - 115V-10 7.3 CFM - 20 HD  
MEETING RM ZONE - B & G - 100-115 - 1/4 HP - 115V-10 20.0 CFM - 15 HD  
DRIVER'S ZONE - B & G - 100-115 - 1/4 HP - 115V-10 4.0 CFM - 8 G.H.G.  
READY RM ZONE - B & G - 100-115 - 1/4 HP - 115V-10 5.0 CFM - 1/2 HD  
APPARATUS RM ZONE - B & G - 100-115 - 1/4 HP - 115V-10 29.2 CFM - 12 HD  
ALL RADIATION CONNECTING TO ONE PIPE LOOP SHALL HAVE TWO MONO-FLO FITTINGS

ALUMINUM - 10 SQ. FT. (GROSS) O.A.I. E COMBUSTION AIR LOUVER W/BIRD SCREEN BY G.C.  
MECHANICAL RM L3  
CONNECT 48" x 24" (ON TOP) & 48" x 4" TO 48" x 2" DUCT RUN 48" x 4" OPEN ENDED INTO EQUIP. RM. RUN TIGHT TO BOTTOM OF BEAMS INTO A/C RM.  
S.R.C. - 32L x 6 x 24H - 5.0 MBH

CONTINUE PIPING THRU EQUIPMENT & A/C ROOMS (CLEAR OF DUCTWORK) TO STORAGE RM L6  
BOILER BURNER UNIT SEE DIAGRAM ABOVE FOR PIPING CONNECTIONS

12" W/B.D.  
48" x 24" OPEN ENDED O.A.I. W/BIRD SCREEN & M.D.  
RUN MAIN SUPPLY DUCT TIGHT TO BOTTOM OF BAR JOISTS & BEAMS. MAXIMUM CLEARANCE MUST BE MAINTAINED BELOW BOTTOM OF DUCT IN BANQUET RM FOR PIPING & WORK OF TRADES. MEETING ROOM AIR HANDLER - EXTEND TRAPPED CONDENSATE DRAIN INTO F.F.D.  
A/C ROOM L5  
13" W/M.D.  
CONTINUE PIPING THRU A/C ROOM (CLEAR OF DUCTWORK) TO BOILER IN EQUIPMENT RM  
UPPER LEVEL DRIVER'S RM ZONE  
LOWER LEVEL LOBBY ZONE  
COMMON RETURN FOR LOBBY & READY RM ZONES - 1/2"  
UPPER LEVEL APPARATUS RM ZONE  
STORAGE RM - L6  
F.R.C. 32 x 4 - 24H 3.8 MBH




## DETAIL OF RECESSED & SEMI-RECESSED CONVECTORS

### NOTES

- CONVECTOR DEPTH - 4" = 1/16" PROJECTION INTO RM  
O" = 2 1/2"  
B" = 4 1/2"
- INSULATE BACK TOP & SIDES OF ALL S.R.C. WITH 1/2" THICK FIBERGLASS INSULATION.
- PIPING ARRANGEMENT TO CABINET HEATERS, FIN-TUBE & BASE BOARD RADIATION SAME AS CONVECTORS.
- CABINET HEATERS - C.H. #1, #2, #3 & 4 SIZE 0.2 GPM - 11 CFM 200 W.P.D. - 0.2 CAPACITY - 14.5 MBH AT LOW SPEED 700 RPM - 200 E.W.T.E 600 F
- C.H. #1 - SEMI-RECESSED - PROJECTION DEPTH - 4 3/4" - H46  
C.H. #2 & #3 - FULLY RECESSED - PROJECTION DEPTH - 3 3/8" - H46  
C.H. #4 - FREE STANDING - B-12  
OVERALL DEPTH OF CH'S #1, #2 & #3 - 9 1/8" CH #4 - 9" B-12  
OVERALL HEIGHT OF CH'S #1, #2 & #3 - 28" CH #4 - 25"
- ALL CABINET HEATERS SHALL HAVE 3 SPEED SWITCH & THERMOSTAT UNIT MTD EX. CH #3. THERM. REMOTE.
- CABINET HEATERS, FIN-TUBE RADIATORS & CONVECTORS BASED ON TRANE
- FIN-TUBE RADIATOR - TYPE 12TA - 12 ROW ELEMENT - 1 1/4" COPPER - ALUMINUM - SERIES - 200 FINS - 1/12" H. ENCLOSURE
- BASE BOARD RADIATOR - VULCAN - STYLE 1000B

VERIFY WALL THICKNESS FOR EACH CABINET HEATER AND CONVECTOR INSTALLATION TO DETERMINE DEPTH OF RECESS AND PROJECTION OF FRONT PANEL BEFORE ORDERING.

## PLAN - LOWER LEVEL



FOR CONSTRUCTION

ADDENDUM #1 6-27-79

BEACON COMMUNITY DEVELOPMENT AGENCY  
100 WOLCOTT AVENUE  
BEACON, NEW YORK

BEACON FIREHOUSE IMPROVEMENTS

TOMPKINS HOSE COMPANY

LOWER LEVEL PLAN

the office of ira kessler architect  
432 Main St. Beacon, NY 12508 (914) 831-7070

DRAWING NUMBER  
**HVAC-1**

SCALE 1/8" = 1'-0" PROJECT NO. 7702 C DRAWN BY P.G. DATE JUNE 1, 1979



CENTRIFUGAL ROOF EXHAUSTERS											
FAN	MODEL	CFM	S.P.	H/P	WEIGHT	RF OPNG	DIA.	HT.	CURB	RPM	SERVING
E-1	CE-10-B	660	3/8"	1/2	80 LBS.	13" sq.	25 3/4"	20"	22" sq.	1140	LOWER LEVEL TOILETS
E-2	CE-10-E	1304	1/2"	1/2	40 LBS	11" sq.	21 1/2"	10 1/2"	11" sq.	1050	UPPER LEVEL BATH RM
E-3	CE-10-C	455	1/4"	1/2	80 LBS	13" sq.	25 3/4"	20"	22" sq.	860	UPPER LEVEL TOILET
E-4	CE-10-D	1304	3/8"	1/4	200 LBS	13" sq.	36 1/16"	25"	30" sq.	650	UPPER LEVEL READY RM.

## CENTRIFUGAL EXHAUSTERS

CENTRIFUGAL EXHAUSTERS										
FAN	MODEL	CFM	SP	H.P.	WEIGHT	HEIGHT	WIDE	DEEP	RPM	O.V
E-5	SWB-24	0431	.50	1/2	460 LBS	48 7/8"	40 3/8"	40"	834	1950
E-6	SWB-15	1004	1.25	3/4	200 LBS	29 7/8"	32"	20"	1331	1300
MEETING ROOM		KITCHEN								
MEETING ROOM		KITCHEN								

MEETING ROOM & KITCHEN FANS SHALL HAVE SPRING VIBRATION ISOLATOR HANGERS; MEETING RM FAN W/INLET GUARD  
KITCHEN FAN SHALL HAVE ALUMINUM WHEEL, ACCESS COVER IN SCROLL & DRAIN CONNECTION.

SIDEWALL PROPELLER FAN

E-748 - FANS SHALL BE MOUNTED ON 3/4" PLYWOOD FRAME. PROVIDE FELT GASKET BETWEEN WALL & FRAME

APPARATUS ROOM HEATING & VENTILATING UNIT


TRANS. TORREVENT #T-12 - CFM 0000 - SP. 1/4" - HP. 3 - BHP 2-12 - RPM 053 - 545 FACE COIL VELOCITY.  
UNIT SHALL HAVE FLAT FILTER BOX WITH HIGH VEL. PERMANENT FILTERS & HIGH WATER HTG COIL CAPABLE OF  
HEATING 0000 CFM FROM -4°F TO 40°F WITH 29.2 GPM OF 200 GWT. 20° T.O. WITH A MAX OF 5°F COIL DROP  
THE HEV UNIT SHALL BE PROVIDED WITH SPRING VIBRATION ISOLATOR MOUNTS. -B40 LBS.

READY ROOM ROOF TOP AIR CONDITIONER


TRANS - MODEL - SACA - 75 - T.S.P. - 100 - CFM - 3000 - RPM - 1140 - BHP - 1.87 - H.P. - 2 - ELECTRIC HEATER - 15 KW - ECONOMIZER # PRESSURE RELIEF & ROOF CURB - 1500 LBS. - 228V. 3P. 60 CY. 20 AMP. MAX.

COMMUNICATIONS ROOFTOP AIR CONDITIONER

TRAN - MODEL - SAHA - 20 - CFM - 800 - SP - 142 - RPM - 1075 - H.P. 1/4 - ELECTRIC HEATER - 4.0 K.W.  
ECONOMIZER - FURNISHED BY THE HVAC - CONTR. - 220V. 15 - 1000CY - 80 - AMPS MAX. & ROOF CURB APPROX WT. 100LBS




TYPICAL  
ROOF EXHAUST FAN DETAIL  
NO SCALE



PIPING CONNECTIONS  
TO HOT WATER HEATING COILS  
NO SCALE.

## MEETING ROOM AIR CONDITIONING SYSTEM

[illegible]

FOR CONSTRUCTION	
▲ APPENDUM #1 6-27-79	
BEACON COMMUNITY DEVELOPMENT AGENCY 100 WOLCOTT AVENUE BEACON, NEW YORK	
BEACON FIREHOUSE IMPROVEMENTS TOMPKINS HOSE COMPANY UPPER LEVEL PLAN	
the office of ira kessler architect 432 Main St Beacon, N.Y. 12508 (914) 831-7096	DRAWING NUMBER  HVAC-2
SCALE 1/8" = 1'-0"	PROJECT NO. 7702C
DRAWN BY PC	DATE JUNE 1, 1979





A. C. SMITH & CO.  
OF BRACON, ILL.  
140 MAIN STREET  
BRACON, ILL.  
4-15-81

101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000
-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------

**SECTION 074213.13**  
**FORMED METAL WALL PANELS**

**PART 1 - GENERAL**

1.01 SECTION INCLUDES

- A. Flush-profile, concealed fastener metal wall panels, with related liner panels, metal trim, and accessories.

1.02 RELATED REQUIREMENTS

- A. Division 05 Section "Structural Steel Framing" for steel framing supporting metal panels.
- B. Division 05 Section "Cold-Formed Metal Framing" for cold-formed metal framing supporting metal panels.
- C. Division 07 Section "Thermal Insulation" for thermal insulation installed behind metal panels.
- D. Division 07 Section "Air Barriers" for air barriers within wall assembly and adjacent to wall assembly.
- E. Division 07 Section "Metal Soffit Panels" for soffit panels installed with metal wall panels.
- F. Division 07 Section "Sheet Metal Flashing and Trim" for sheet metal flashing items in addition to items specified in this Section.

1.03 REFERENCES

- A. American Architectural Manufacturer's Association (AAMA): [www.aamanet.org](http://www.aamanet.org):
  - 1. AAMA 621 - Voluntary Specifications for High Performance Organic Coatings on Coil Coated Architectural Hot Dipped Galvanized (HDG) & Zinc-Aluminum Coated Steel Substrates.
  - 2. AAMA 809.2 Voluntary Specification Non-Drying Sealants.
- B. American Society of Civil Engineers (ASCE): [www.asce.org/codes-standards](http://www.asce.org/codes-standards):
  - 1. ASCE 7 - Minimum Design Loads for Buildings and Other Structures.
- C. ASTM International (ASTM): [www.astm.org](http://www.astm.org):
  - 1. ASTM A755 - Specification for Steel Sheet, Metallic Coated by the Hot-Dip Process and Prepainted by the Coil-Coating Process for Exterior Exposed Building Products.
  - 2. ASTM A792/A792M - Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
  - 3. ASTM C920 - Specification for Elastomeric [Joint Sealants](#).
  - 4. ASTM D2244 - Test Method for Calculation of Color Differences from Instrumentally Measured Color Coordinates.
  - 5. ASTM D4214 - Test Methods for Evaluating Degree of Chalking of Exterior Paint Films.
  - 6. ASTM E283 - Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen.



7. ASTM E331 - Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference.
8. ASTM E1592 - Standard Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference.

D. International Accreditation Service (IAS):

1. IAS AC472 Accreditation Criteria for Inspection Programs for Manufacturers of Metal Building Systems, Part B.

#### 1.04 QUALITY ASSURANCE

- A. Manufacturer/Source: Provide metal panel assemblies and accessories from a single manufacturer accredited under IAS AC472, Part B.
- B. Manufacturer Qualifications: Approved manufacturer listed in this Section with minimum five years' experience in manufacture of similar products in successful use in similar applications.
  1. Approval of Comparable Products: Submit the following in accordance with project substitution requirements, within time allowed for substitution review:
    - a. Product data, including certified independent test data indicating compliance with requirements.
    - b. Samples of each component.
    - c. Sample shop drawings from a similar project.
    - d. Project References: Minimum of five installations not less than three years old, with Owner and Architect contact information.
    - e. Sample warranty.
    - f. Certificate of accreditation under IAS AC472 Part B.
  2. Substitutions following award of contract are not allowed except as stipulated in Division 01 General Requirements.
- C. Installer Qualifications: Experienced Installer with minimum of five years' experience with successfully completed projects of a similar nature and scope.
  1. Installer's Field Supervisor: Experienced mechanic supervising work on site whenever work is underway.
- D. Steel Construction Publications: Comply with published recommendations in the following, unless more stringent requirements are indicated.
  1. American Institute of Steel Construction (AISC): "Steel Construction Manual."
  2. American Iron and Steel Institute (AISI): "Cold Formed Steel Design Manual."

#### 1.05 ACTION SUBMITTALS

- A. Product Data: Manufacturer's data sheets for specified products. Include data indicating compliance with performance requirements.
- B. Shop Drawings: Show layouts of metal panels. Include details of each condition of installation, panel profiles, and attachment to building. Provide details at a minimum scale 1-1/2-inch per foot of edge conditions, joints, fastener and sealant placement, flashings, openings, penetrations, and special details. Make distinctions between factory and field assembled work.

1. Indicate points of supporting structure that must coordinate with metal panel system installation.
  2. Include structural data indicating compliance with performance requirements and requirements of local authorities having jurisdiction.
- C. Samples for Initial Selection: For each exposed product specified including sealants. Provide actual material samples representative of manufacturer's full range of colors.
- 1.06 INFORMATIONAL SUBMITTALS
- A. Product Test Reports: Indicating compliance of products with requirements.
  - B. Qualification Information: For Installer firm and Installer's field supervisor.
  - C. **Florida State Building Code Certificate:** Indicating that products comply with requirements of Florida State Building Code. [www.floridabuilding.org/pr/pr\\_app\\_srch.aspx](http://www.floridabuilding.org/pr/pr_app_srch.aspx)
  - D. Manufacturer's warranty: Unexecuted sample copy of manufacturer's warranty.
- 1.07 CLOSEOUT SUBMITTALS
- A. Maintenance data.
  - B. Manufacturer's Warranty: Executed copy of manufacturer's warranty.
- 1.08 DELIVERY, STORAGE, AND HANDLING
- A. Protect products of metal panel system during shipping, handling, and storage to prevent staining, denting, deterioration of components or other damage. Protect panels and trim bundles during shipping.
    1. Deliver, unload, store, and erect metal panels and accessory items without misshaping panels or exposing panels to surface damage from weather or construction operations.
    2. Store in accordance with Manufacturer's written instruction. Provide wood collars for stacking and handling in the field.
    3. Shield foam insulated metal panels from direct sunlight until installation.
- 1.09 WARRANTY
- A. Special Manufacturer's Warranty: On manufacturer's standard form, in which manufacturer agrees to repair or replace metal panel assemblies that fail in materials and workmanship within one year from date of Substantial Completion.
  - B. Special Panel Finish Warranty: On Manufacturer's standard form, in which Manufacturer agrees to repair or replace metal panels that evidence deterioration of factory-applied finish within the warranty period, as follows:
    1. **Fluoropolymer Two-Coat System:**
      - a. Basis of Design System: **MBCI, Signature 300.**
      - b. Color fading in excess of 5 Hunter units per ASTM D2244.
      - c. Chalking in excess of No. 8 rating per ASTM D4214.
      - d. Failure of adhesion, peeling, checking, or cracking.
      - e. Warranty Period: 40 years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.01 MANUFACTURER

- A. Basis of Design Manufacturer: **MBCI Metal Roof and Wall Systems, Division of NCI Group, Inc.**; Houston TX. Tel: (877)713-6224; Email: [info@mbci.com](mailto:info@mbci.com); Web: [www.mbc.com](http://www.mbc.com).
  - 1. Provide basis of design product, or comparable product approved by Architect prior to bid.

### 2.02 PERFORMANCE REQUIREMENTS

- A. General: Provide metal panel system meeting performance requirements as determined by application of specified tests by a qualified testing facility on manufacturer's standard assemblies.
- B. Structural Performance: Provide metal panel assemblies capable of withstanding the effects of indicated loads and stresses within limits and under conditions indicated, as determined by ASTM E1592:
  - 1. Wind Loads: Determine loads based on uniform pressure, importance factor, exposure category, and basic wind speed indicated on drawings.
    - a. Wind Negative Pressure: Certify capacity of metal panels by actual testing of proposed assembly.
  - 2. Deflection Limits: Withstand inward and outward wind-load design pressures in accordance with applicable building code with maximum deflection of 1/120 of the span with no evidence of failure.
  - 3. Seismic Performance: Comply with ASCE 7 Sections 9, "Earthquake Loads."
- C. **Florida State Building Code Compliance:** Provide metal roof and wall panels complying with requirements for installation under Florida State Building Code outside of high velocity wind zone.
- D. Wall Panel Air Infiltration, ASTM E283:
  - 1. No air infiltration at static-air-pressure difference of 1.57 lbf/sq. ft. (75 Pa).
- E. Wall Panel Water Penetration Static Pressure, ASTM E331: No uncontrolled water penetration at a static pressure of 6.24 lbf/sq. ft. (300 Pa).
- F. Thermal Movements: Allow for thermal movements from variations in both ambient and internal temperatures. Accommodate movement of support structure caused by thermal expansion and contraction. Allow for deflection and design for thermal stresses caused by temperature differences from one side of the panel to the other.

### 2.03 FORMED METAL WALL PANELS

- A. Flush-Profile, Concealed Fastener Metal Wall Panels: Structural metal panels consisting of formed metal sheet with vertical panel edges and flat pan, with flush joints between panels, field assembled with nested lapped edges, and attached to supports using concealed fasteners.
  - 1. Basis of Design: **MBCI, FW-120 Panel.**



2. Aluminum-Zinc Alloy-Coated Steel Sheet: ASTM A792/A792M, structural quality, Grade 50, Coating Class AZ50 (Grade 340, Coating Class AZM150), pre-painted by the coil-coating process per ASTM A755/A755M.
  - a. Nominal Thickness: 22 gage coated thickness, with smooth surface.
    - 1) Exterior Finish: Fluoropolymer two-coat metallic color system.
    - 2) Color: As selected by Architect from manufacturer's standard colors.
3. Panel Width: 12 inches (305 mm).
4. Panel Thickness: 1-1/2 inch (38 mm).

#### 2.04 MISCELLANEOUS MATERIALS

- A. General: Provide complete metal panel assemblies incorporating trim, copings, fasciae, gutters and downspouts, and miscellaneous flashings. Provide required fasteners, closure strips, and sealants as indicated in manufacturer's written instructions.
- B. Flashing and Trim: Match material, thickness, and finish of metal panels.
- C. Panel Fasteners: Self-tapping screws and other acceptable fasteners recommended by metal panel manufacturer. Where exposed fasteners cannot be avoided, supply corrosion-resistant fasteners with heads matching color of metal panels by means of factory-applied coating, with weathertight resilient washers.
- D. Panel Sealants:
  1. Factory-Applied Seam Sealant: Manufacturer's standard hot-melt type.
  2. Concealed [Joint Sealants](#): Non-curing butyl, AAMA 809.2.
  3. Elastomeric [Joint Sealants](#): Urethane sealant, single-component, ASTM C920 Type S, Grade NS, Class 25, Use NT, A, M, G, O.
  4. Foam Tape: Manufacturer's standard self-adhering type.

#### 2.05 FABRICATION

- A. General: Provide factory fabricated and finished metal panels, trim, and accessories meeting performance requirements, indicated profiles, and structural requirements.
- B. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's written instructions, approved shop drawings, and project drawings.

#### 2.06 FINISHES

- A. Finishes, General: Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
- B. Fluoropolymer Two-Coat System: 0.2 – 0.3 mil primer with 0.7 - 0.8 mil 70 percent PVDF fluoropolymer color coat, AAMA 621.
  1. Basis of Design: **MBCI, Signature 300.**

## PART 3 - EXECUTION

### 3.01 EXAMINATION

- A. Examine metal panel system substrate with Installer present. Inspect for erection tolerances and other conditions that would adversely affect installation of metal panels.
  - 1. Inspect framing that will support insulated metal panels to determine if support components are installed as indicated on approved shop drawings and are within tolerances acceptable to metal panel manufacturer and installer. Confirm presence of acceptable framing members at recommended spacing to match installation requirements of metal panels.
- B. Correct out-of-tolerance work and other deficient conditions prior to proceeding with insulated metal panel installation.

### 3.02 METAL PANEL INSTALLATION

- A. Concealed-Fastener Formed Metal Panels: Install metal panel system in accordance with manufacturer's written instructions, approved shop drawings, project drawings, and referenced publications. Install metal panels in orientation, sizes, and locations indicated. Anchor panels and other components securely in place. Provide for thermal and structural movement.
- B. Fasten metal panels to supports with fasteners at each location indicated on approved shop drawings, at spacing and with fasteners recommended by manufacturer. Fasten panel to support structure through leading flange. Snap-fit back flange of subsequent panel into secured flange of previous panel. Where indicated, fasten panels together through flush-fitted panel sides.
  - 1. Cut panels in field where required using manufacturer's recommended methods.
  - 2. Dissimilar Materials: Where elements of metal panel system will come into contact with dissimilar materials, treat faces and edges in contact with dissimilar materials as recommended by metal panel manufacturer.
- C. Attach panel flashing trim pieces to supports using recommended fasteners and joint sealers.
- D. Joint Sealers: Install liquid sealants where indicated and where required for weatherproof performance of metal panel assemblies.
  - 1. Seal panel base assembly, openings, panel head joints, and perimeter joints using joint sealers indicated in manufacturer's instructions.
  - 2. Seal perimeter joints between window and door openings and adjacent panels using elastomeric joint sealer.
  - 3. Prepare joints and apply sealants per requirements of Division 07 Section "[Joint Sealants](#)."

### 3.03 ACCESSORY INSTALLATION

- A. General: Install metal panel accessories with positive anchorage to building and weather tight mounting; provide for thermal expansion. Coordinate installation with flashings and other components.
  - 1. Install components required for a complete metal panel assembly, including trim, copings, flashings, sealants, closure strips, and similar items.

2. Comply with details of assemblies utilized to establish compliance with performance requirements and manufacturer's written installation instructions.
3. Set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently weather resistant.

#### 3.04 CLEANING AND PROTECTION

- A. Clean finished surfaces as recommended by metal panel manufacturer.
- B. Replace damaged panels and accessories that cannot be repaired to the satisfaction of the Architect.



**THIS PAGE LEFT BLANK INTENTIONALLY**

**END OF SECTION**

SECTION 233713  
DIFFUSERS, REGISTERS, AND GRILLES

PART 1 GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SUMMARY

- A. Section Includes:
  - 1. Rectangular and square ceiling diffusers.
  - 2. Fixed face registers and grilles.
- B. Related Sections:
  - 1. Division 23 Section, "Air Duct Accessories" for fire and volume control dampers not integral to diffusers, registers, and grilles.

1.03 SUBMITTALS

- A. Product Data: For each type of product indicated, include the following:
  - 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static pressure drop, and noise ratings.
  - 2. Diffuser, Register, and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.
  - 3. Manufacturer's standard color chart for finish selection.
- B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from Installers of the items involved:
  - 1. Ceiling suspension assembly members.
  - 2. Method of attaching hangers to building structure.
  - 3. Size and location of initial access modules for acoustical tile.
  - 4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
  - 5. Duct access panels.
- C. Source quality control reports.

PART 2 PRODUCTS

2.01 REGISTERS AND GRILLES

- A. Fixed Face Registers and Grilles:
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Anemostat Products; a Mestek company.
    - b. Carnes.
    - c. Hart & Cooley Inc.
    - d. Krueger.
    - e. Nailor Industries Inc.
    - f. Price Industries.
    - g. Titus.
    - h. Tuttle & Bailey.

2. Material: Steel with 1-1/4" wide border on all sides and a minimum border gauge of 20. Corners shall be assembled with full penetration resistance welds. Blades shall have a minimum gauge of 20 with a fixed deflection of 45 degrees.
3. Finish: Baked enamel, color as selected by architect.
4. Face Arrangement: Aeroblade blades with 3/4" blade spacing. Blades shall be parallel to the long dimension.
5. Damper Type (Registers Only): Adjustable opposed blade.

## 2.02 CEILING DIFFUSERS

### A. Rectangular and Square Ceiling Diffusers:

1. Devices shall be specifically designed for variable-air-volume flows.
2. Material: Steel.
3. Finish: Baked enamel, white.
4. Face Size: 24 by 24 inches.
5. Mounting: T-bar.
6. Pattern: Adjustable.
7. Dampers: Butterfly.
8. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - a. Anemostat Products; a Mestek company.
  - b. Carnes.
  - c. Hart & Cooley Inc.
  - d. Krueger.
  - e. Nailor Industries Inc.
  - f. Price Industries.
  - g. Titus.
  - h. Tuttle & Bailey.

### B. Louver Face Diffuser:

1. Devices shall be specifically designed for variable-air-volume flows.
2. Material: Steel.
3. Finish: Baked enamel, white.
4. Mounting: Surface.
5. Pattern: One-way, Two-way, Two-way corner, Three-way, Four-way core style.
6. Dampers: Opposed blade.
7. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - a. Anemostat Products; a Mestek company.
  - b. Carnes.
  - c. Hart & Cooley Inc.
  - d. Krueger.
  - e. Nailor Industries Inc.
  - f. Price Industries.
  - g. Titus.
  - h. Tuttle & Bailey.



2. Material: Steel with 1-1/4" wide border on all sides and a minimum border gauge of 20. Corners shall be assembled with full penetration resistance welds. Blades shall have a minimum gauge of 20 with a fixed deflection of 45 degrees.
3. Finish: Baked enamel, color as selected by architect.
4. Face Arrangement: Aeroblade blades with 3/4" blade spacing. Blades shall be parallel to the long dimension.
5. Damper Type (Registers Only): Adjustable opposed blade.

## 2.02 CEILING DIFFUSERS

### A. Rectangular and Square Ceiling Diffusers:

1. Devices shall be specifically designed for variable-air-volume flows.
2. Material: Steel.
3. Finish: Baked enamel, white.
4. Face Size: 24 by 24 inches.
5. Mounting: T-bar.
6. Pattern: Adjustable.
7. Dampers: Butterfly.
8. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - a. Anemostat Products; a Mestek company.
  - b. Carnes.
  - c. Hart & Cooley Inc.
  - d. Krueger.
  - e. Nailor Industries Inc.
  - f. Price Industries.
  - g. Titus.
  - h. Tuttle & Bailey.

### B. Louver Face Diffuser:

1. Devices shall be specifically designed for variable-air-volume flows.
2. Material: Steel.
3. Finish: Baked enamel, white.
4. Mounting: Surface.
5. Pattern: One-way, Two-way, Two-way corner, Three-way, Four-way core style.
6. Dampers: Opposed blade.
7. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - a. Anemostat Products; a Mestek company.
  - b. Carnes.
  - c. Hart & Cooley Inc.
  - d. Krueger.
  - e. Nailor Industries Inc.
  - f. Price Industries.
  - g. Titus.
  - h. Tuttle & Bailey.

### 2.03 SOURCE QUALITY CONTROL

- A. Verification of Performance: Rate diffusers, registers, and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

## PART 3 EXECUTION

### 3.01 EXAMINATION

- A. Examine areas where diffusers, registers, and grilles are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.02 INSTALLATION

- A. Install registers, and grilles level and plumb.
- B. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

### 3.03 ADJUSTING

- A. After installation, adjust registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

END OF SECTION





the Palombo Group

MA Mitchell Associates  
Architects PLLC

**Addition & Renovation for Beacon Fire Station**  
**03/29/2023 Pre-Bid Walk Thru Meeting Sign In-Sheet**

Name	Company	Phone	Email	Contract Bidding On
Kyle Cuomo	MA Hudson CM	(845) 294-9230	Estimating@Mthudson.com	GC/SC
DT Sadowski	"	"	"	"
Eric Schmuck	CB Strain	(845) 454-6600	ecs@cbstrain.com	Mech/Plbg
Jaeger Jordan	Butler	845-769-7413	ESTIMATING@	GC/SLITE
Ryan Stratton	Butler	315-731-7680	Butler construction group, inc	
Adam Timmons	W3TE	845 225 9690	ATTY@W3TE.COM	CM/ENR
Tony Russo	LAKEVIEW P.C.	845-294-3700	JDR@lakeview.pc	MAINT
MARK MESSINA	BEN LICONE	845.462.2800	ESTIMATING@BENLICONES.COM	SITE
<del>Mike Sica</del>	MAA			
JEFF RIDGE	Black Tie	845 267 3117	rod@blacktietrust.com	26
Chyn's White	City of Beacon			
Ben Shuman	City of Beacon			
Alex Meyer	Meyer Contracting	845 261 5176	Alex@meyercontracting.com	GC
Tom Christner	The Palombo Group			
Jose Otero	The Palombo Group			



**Addition & Renovation for Beacon Fire Station**  
**03/29/2023 Pre-Bid Walk Thru Meeting Sign In-Sheet**

Name	Company	Phone	Email	Contract Bidding On
Mike Roth	JSPathi Roofing	732 447 7246	Methu@tectamcnc.com	Roofing
Jim Piazza	Nivein Construct	914-489-2358	Jim@niveinconstruct.com	GC + SIK
Paul Gaudet	DALANO ASSOC	845 223-5115	fganga@casidy.com	GC
Dave Pittern	SRI Fire Sprinkler	914-659-6206	Dave@srifiresprinkler.com	FS
Mike Botkin	KEY Construction	845-454-1192-105	Attaf@keyconstruction.com	GC
John A. Malin	MANBOLD	Matt Malin	845-234-1020	ESTIMATING @ MANBOLD.COM
Peter Britanga	Empire One Group	914-6565-676	pbritang@empireone.com	GENERAL MGMT. COM
Martin Kendl	Oes Industries Inc		mkennd@oesindustries.com	GC
Oes		914-538-0654	Estimating@oesindustries.com	Steel